

BRUHAT BANGALORE MAHANAGARA PALIKE
Project Division, Dasarahalli Zone
SCHEDULE-B

Tender Number:- BBMP/2019-20/BD/WORK_INDENT35893

Tender Name:- Improvements of Roads and Drains at Shettyhalli and Surrounding area in Ward No-12 Project Division Dasarahalli (Package-1).

SNo	Item Name	Unit	Quantity	Yogesh (NANDI)	
				Quoted Rate	Total Amount
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications Including loading and unloading with 5km lead and Complete as per Engineer in-charge direction	Cum	9196.44	220.40	2025895.38
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs. with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications and Complete as per Engineer in-charge direction	Cum	1381.21	5421.90	7488782.50
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specifications do- Wall & bottom thickness 15cm and Complete as per Engineer in-charge direction	Cum	2094.72	7070.20	14810089.34
4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications and Complete as per Engineer in-charge direction	Tonne	140.86	72326.98	10187978.40
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, and Complete as per Engineer in-charge direction	Sqm	5260.98	2208.00	11616243.84


For M/s. NANDI CONSTRUCTION


CONTRACTOR
Partners

EXECUTIVE ENGINEER
PROJECT DIVISION
DASARAHALLI ZONE

	Item Name	Unit	Quantity	Yogesha (NANDI)	
				Quoted Rate	Total Amount
6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:1.5:3 and jelly 20mm charges of machinery, loading, unloading, lead and lift, transportation etc, complete and Complete as per Engineer in-charge direction	Sqm	58.80	5241.00	308170.80
7	Providing and laying Plain / Reinforced Cement Concrete design mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates @ 0.47cum, with superplasticizer @3lts confirming to IS9103-1999 Reaffirmed-2008, Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications Complete as per Engineer in-charge direction	Cum	291.06	5294.70	1541075.38
8	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete Complete as per Engineer in-charge direction	No	7187.00	432.48	3108233.76
9	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications Complete as per Engineer in-charge direction	Sqm	1287.90	84.80	109213.92
10	Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embarkment location to a lead of 1km and complete as per specifications. Including loading and unloading with 5km lead Complete as per Engineer in-charge direction	Cum	194.22	69.06	13412.83
11	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, HOM of machinery complete as per specifications. Complete as per Engineer in-charge direction	Sqm	454.40	6.36	2889.98
12	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications	Cum	64.74	1994.92	129151.12

For M/s. NANDI CONSTRUCTION



CONTRACTOR
Partners


EXECUTIVE ENGINEER
PROJECT DIVISION
DASARAHALLI ZONE

Item Name	Unit	Quantity	Yogesha (NANDI)	
			Quoted Rate	Total Amount
13 Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum, Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour, hire charges of machineries, all lead & lift charges etc., complete as per specifications.	Cum	87.46	5210.96	455750.56
14 Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. Complete as per Engineer in-charge direction	Sqm	647.40	72.08	46664.59
Total Amount				51844552.42


 Executive Engineer,
 Project Division Dasarahalli
 BBMP Bangalore

For M/s. NANDI CONSTRUCTION


 CONTRACTOR
 Partners


 EXECUTIVE ENGINEER
 PROJECT DIVISION
 DASARAHALLI ZONE